



ISPS Code Compliant
ISO 9001 : 2015 Certified



Port
Par - Excellence
चेनै पोर्ट ट्रस्ट

CHENNAI PORT TRUST

Fax : +91-44-25361228
Phone : +91-44-25312000
: +91-44-25362201

प्रशासनिक कार्यालय
ADMINISTRATIVE OFFICE
राजाजी सालै, चेन्नै - 600 001.
Rajaji Salai, Chennai - 600 001.
Website : www.chennaiport.gov.in

No.MEE/V3/019/2020/Dy.CME(MP&OH)

Dated 24.01.2022

To

M/s.Projects & Development India Limited,
Rabiya Building, 1st Floor,
N.No.238, O.No.187, Royapettah High Road,
Mylapore, Chennai - 600 004.

Sir,

Sub: Electrical Audit- Carrying out of Electrical Safety Audit at
BD-I and BD-III at oil Jetty of Chennai Port Trust – Reg.
Ref: Your letter no.PDIL-Chennai Port –EA dt.24.12.2021.

Your Offer for the above work is accepted as detailed below:-

1. Scope of work:-

Electrical Safety Audit

The audit work shall be conducted as per the scope of work given below and as per relevant IS 3043. OISD 156 & OISD 145, and IE Rules. Checking and examination of the following equipment shall be done and GAP Analysis report shall be submitted for necessary action.

1. High Voltage VCB operation.
2. HV Panel-Mechanical/ Electrical closing and tripping of breakers.
3. Power Transformers-Cable terminations, OTI, WTI and Buccholz Relay, Silica-gel breather etc.
4. PCC/PMCC- Cable termination, Circuit Breakers, Operation of SFU modules and Relays, Indication lamps, interlocks etc.
5. Main Lighting Board-cable termination, SFU and fuse ratings as per SLD.
6. DG Sets along with its associated control panel.

7. FLP Motors, Starters, Pushbutton Stations, LDB, Lighting Fixtures, Junction Boxes etc, Cable connections, internal earthing and flame paths.
8. Earth pits along with grid on random basis for continuity of earth connections to the equipment.
9. IR values of outgoing cables on random basis.
10. Hardware's used in the equipment and in cable terminations.

II. Fees

Lumpsum Rs. 80,000/- (Rupees Eighty thousand only) plus GST @ 18 % (as per GOI norms).

III. Chennai Port's Obligations:

M/s Chennai Port shall provide necessary assistance like Electrician, Instruments like tong tester, earth megger, set of tools like spanner sets, screw drivers, Allen keys of different sizes etc. If required, shut down should be arranged to examine the electrical equipment. M/s. Chennai port shall arrange necessary permits.

IV. Completion period:

The job shall be taken up and will be completed within one month from the date of receipt of order.

V) Payment Terms:


Two copies of 'Electrical Audit/ Gap Analysis' report shall be submitted along with invoice and 100% payment will be released within 30 days from the date of submission of invoice.

You are requested to acknowledge receipt of this work order and commence the work immediately.

Nodal officer for this work is Executive Engineer(Mech)MP&OH.
Contact No.25312570 and e-mail:-exm_od@chennaiport.gov.in

Thanking you,

Yours faithfully,


(T.KARUNANITHY)
Executive Engineer (M)MP&OH